Item No.	Description of work	Unit	Rate	Quantity
	Construction of a C. I. pipe sluice of 3″ dia. cill 48·00.		Rs. a. p.	
1	Cutting open the bund and refixing the same with watering and consolidation	C.yd.	0 6 0	16
2	Earthwork excavation for foundation	,,	0 4 0	5
3	Providing rough stone in clay in case the foundation is found to be loose and slushy including earthwork excavation from 45·00 to 43·00	,,	3 0 0	3
4	Stone jelly concrete in cement mortar 1 : 4 : 8 ..	C.ft.	0 7 0	133
5	Size stone in cement mortar 1 : 5	,,	0 8 0	97
6	Stone jelly concrete in cement mortar 1 : 2 : 4 ..	,,	1 0 0	36
7	Burnt stone slabs 6″ thick dressed and fixed in cement mortar. Gibbet and guide slabs	S.ft.	0 12 0	36
8	Drilling holes in slabs	No.	1 0 0	2
9	Providing 3″ dia. R. C. C. pipes including fixing, etc., complete	R.ft.	1 0 0	36
10	Providing a junglewood platform from the bund to the sluice 2′ wide with wooden beams, slab support, etc...	No.	15 0 0	1
11	Providing and fixing T. wood plug with iron rod and locking arrangements, etc.	No.	10 0 0	1
12	Rough stone work revetment to front slope ..	C.yd.	2 8 0	24
13	Cement pointing and plastering to masonry, etc. ..	L. S.	..	..
	Waste Weir length 10′ R. L. 51·50.			
1	Earthwork excavation for foundation of body wall ..	C.yd.	0 4 0	3
2	Stone jelly concrete in cement mortar 1 : 4 : 8 for foundation of body wall	C.ft.	0 7 0	14½
3	Size stone in cement mortar 1 : 5 body wall	,,	0 8 0	32
4	Burnt stone slabs 6″ thick dressed and fixed in cement mortar with joints, coping slabs, etc.	S.ft.	0 12 0	47
5	Rough stone work revetment	C.yd.	2 8 0	19
	Miscellaneous Works.			
1	Clearing both thick and thin jungle on slopes of bund ..	L. S.	..	..
2	Excavating and clearing the check drain on the right side of the bund	C.yd.	0 4 0	33
3	Rough stone pitching to the halla at the bund portion ..	,,	2 8 0	22
4	Miscellaneous and unforeseen items	L. S.	..	..

D. A. HUKERI,
Executive Engineer.

KADUR DIVISION.

Notification dated 29th May 1940.

1. Sealed tenders will be received at the Office of the Executive Engineer, Kadur Division, Chikmagalur, up to 3 P.M. on 11 June 1940, for the work of construction and lay out of Bus Stand in Kadur Town.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Kadur Division, on payment of annas four per each copy should be addressed to the Executive Engineer, Kadur Division, Chikmagalur, in a sealed cover and superscribed as "Tender for the work of construction and ley out of Bus Stand in Kadur Town." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a Treasury challan of Rs. 290 (in words) rupees two hundred and ninety only for having credited the earnest money to 17 (*a*) P.W.D. Deposits. The earnest money of the successful tenderer will be retained as security deposit for the due fulfilment of the contract. Such a deposit in cash will not carry any interest. Tenders unaccompanied by earnest money will not be accepted.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 11th June 1940 at Chikmagalur. The final acceptance of the tender will rest with the Superintending Engineer who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental schedule contract form for the due fulfilment of the contract.

6. Failure to comply with the condition 5 above, or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Chikmagalur, on all working days between 11 A.M. and 5 P.M.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made, the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to, and the number of corrections, if any, in each page, noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department schedule of rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof, or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions or additions at the discretion of the Executive Engineer or his representative. The tendered rates will hold good for any quantity whether higher or lower than those given in the enclosed schedule.

17. The works should be completed and handed over in a tidy condition to the Public Works Department by the end of September 1940, failing which the Executive Engineer may, at his discretion, levy a penalty of Rs. 100 per fortnight which will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. "Chamundi" brand cement must be used for this work.

23. The contractor should arrange for the payment of royalty and tolls.

Note.—(*a*) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labour required in setting out the works.
(2) Provide all necessary scaffolding, centering, labour and appliances for hoisting.
(3) Provide mortar mills and sheds, to keep materials under cover and also for workmen.
(4) Arrange for protecting work during inclement weather.
(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.

(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.

(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.

(8) Provide arrangements for pumping and baling of water from excavations and foundations, wherever and whenever necessary with his own pumping apparatus, including necessary leading drains, slump pits, etc.

(9) Afford facilities to any other parties employed upon the work by the P. W. D., so that their work may proceed during the progress of the contract and give such persons the use of ordinary scaffolding and ladders.

(10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents and if necessary, provide for the same by insurance at the proper time.

Note—(*b*) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

Abstract of quantities for the construction and lay-out of Bus Stand at Kadur.

No.	Items of work	Unit	Rate	Quantity	Cost
	I. CONSTRUCTING BUS STAND.		Rs. a. p.		Rs.
1	Earthwork excavating foundations and filling in basement with watering and consolidating ..	C.yd.	0 3 0	66	
2	Burnt stone jelly concrete in lime mortar 1 : 2 : 4 for foundations with tamping in layers not more than 6″ thick	C.ft.	0 4 0	602	
3	Burnt size stone in mud for foundations with bond stones 6′ apart	C.ft.	0 4 0	823	
4	Burnt size stone in mud for basement with bond stone 6′ apart including all quoins neatly dressed 2″ wide	C.ft.	0 4 0	169	
5	Burnt stone slabs 6″ thick for basement and step including two lines dressing on exposed faces and one line dressing on all other faces ..	S.ft.	0 10 0	396	
6	Burnt brick in mud superstructure	C.ft.	0 4 0	894	
7	Burnt brick in lime mortar superstructure ..	C.ft.	0 5 0	132	
8	Burnt stone slabs 6″ thick one line dressed on all exposed faces for lintels of doors, sills and lintels of windows and ventilators and stone plates below roof level	S.ft.	0 8 0	130	
9	Reinforced cement concrete 1 : 2 : 4 pillars, 10″ dia. 10 ft. high with 1½ per cent reinforcement, with groves cut at top and bottom as per design including cement plastering ½″ thick ..	C.ft.	3 8 0	109	
10	Rolled steel girders as per B.S.S. including lifting and hoisting and boxing with cement mortar and terrace brick reinforced with galvanized steel tex tied from above with one coat of anti-corrosive painting with mouldings as per design.	Cwt.	18 0 0	19·15	
11	Reinforced cement concrete pre cast seat as per design, 32′ length, 3¾ ft. wide, 3 ft. high with cement plastering, etc., complete	S.ft.	3 8 0	120	
12	Reinforced cement concrete chejja 3′ projection from the wall, 3″ thick, 1½′ anchorage into the wall over windows and doors of the restaurant as lintels	S.ft.	0 12 0	70	
13	Teakwood doors 4″×5″ frame with 1¼″ thick panelled shutters, with iron hinges, hooks and stoppers, including brass hasps, staples and handle, etc., complete including two coats of approved varnish with teakwood counters fixed to each door as per design	S.ft.	2 0 0	85	

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
14	Teakwood door 3″×4½″ framed with 1¼″ thick panelled shutters with usual iron fittings including two coats of approved paints	S.ft.	1 12 0	26	
15	Teakwood windows 3″×4″ frame with 1″ thick panelled shutters in four halves to open outside with steel parliamentary hinges, hooks and brass rings 2″ dia., etc., including two coats of approved paints	,,	2 0 0	30	
16	Teakwood ventilators 3″×4″ frame with glazed shutters in two halves including usual iron fittings and two coats of approved paint ..	,,	1 8 0	9	
17	Roofing with reinforced cement concrete terrace with sufficient reinforcements, to take a superload of 60 lbs. per S.ft., with R.C.C. Chajja projected from roof alround the building 4 ft. width having 4″ thick at the end including chunam plastering on both sides of the terrace.	Sqr.	70 0 0	12·14	
18	Flooring with cement concrete 1 : 2 : 4—1½″ thick, on a bed of 3″ thick lime concrete, with topping of red cement mortar ½″ thick, finished smooth and cut to tile pattern	,,	20 0 0	12·52	
19	Flooring with burnt stone slabs 3″ thick, top surface and joints one line dressed on a bed of 3″ thick lime concrete with cement pointing to the slabs	,,	40 0 0	0·50	
20	Plastering the walls of lavatories and restaurant with chunam plaster	,,	4 0 0	24·45	
21	Painting the basement with cement and lining nicely (1 : 3)	,,	5 0 0	4·45	
22	White washing, two coats	Sqr.	0 4 0	48·26	
23	R.C. louvred panels between pillars of hall 15″ depth, each louvre being 2″ slant depth and ½″ thick as per design	S.ft.	1 8 0	98	
24	Cement perforated ventilators as per design over-doors and windows of restaurant	,,,	1 0 0	5	
25	Notice Board plastered with ½″ thick cement with border as per design	,,	0 4 0	28	
26	Providing moulding 6″ thick as per design alround the restaurant at the roof level	R.ft.	0 6 0	55	
27	Trellis work with creepers at the rear having 2″ dia., galvanized vertical pipes fixed in lime concrete and horizontal pipes 2″ dia., fixed to verticals both at top and bottom for frames and the rectangular compartments to be fitted with galvanized wire-netting with 3″ square opening, etc., complete as per design	S.ft.	0 4 0	427	
28	Paving the rear open yard with 4″ thick burnt stone slabs over a gravel bed of 6″ thick and the top surface one line dressed with cement pointing	,,	0 7 0	403	
	II. LAY-OUT OF BUS STAND, FORMING LAWNS, FENCING, ETC.				
1	Supplying and fixing Bhadravati creosoted wooden railings with 4″×4″ stout pillars at an interval of 6′ c to c.	R.ft.	0 6 0	1,004	

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
2	Providing lawns with turfing, etc., complete ..	S.yd.	0 1 0	1,651	
3	Providing hedging alround the Bus Stand including earthwork excavation, etc.	R.ft.	0 1 0	750	
4	Providing and fixing curb stones alround lawn and park	,,	0 4 0	742	
5	Pick-forming, collecting, breaking and staking quartz metal and consolidating with gravel ..	S.yds.	0 2 0	1,371	
6	Supplying and fixing R.C.C. wicket posts ..	No.	2 0 0	8	
7	(*a*) Earthwork excavation for foundation in hard soil and filling in the sides	C.yd.	0 3 6	5	
	(*b*) Stone jelly in lime mortar concrete 1 : 2 ..	C.ft.	0 4 0	33	
	(*c*) Size stone in mud for foundation including quoin dressing	,,	0 4 0	174	
	(*d*) Burnt stone slabs of 6" thick, two line dressed and fixed in cement mortar including champerring	S.ft.	0 12 0	74	
	(*e*) Cement pointing to basement	Sqr.	5 0 0	2·28	
	(*f*) Supplying and fixing iron gates as per approved design	S.ft.	1 12 0	32	
	II ALTERNATIVE ITEMS THAT MAY BE FOUND DURING EXECUTION, CONSISTENT WITH CHARGES THAT MAY BE MADE.				
1	Providing, castings and curing R.C.C. beams with reinforcements as per design including centering changes including finishing up exposed faces with nice cement plaster (1 : 3) for a span of 6', etc., complete	C.ft.	2 4 0	..	

M. A. RAMANUJAM,
Executive Engineer.

CHITALDRUG DIVISION.

Abstract Notification dated 20th May 1940.

The attention of the public is invited to the Notification calling for tenders for "*Restoring Heggere Hirekere Tank, Register No.* 31 *of Hosadurga Taluk,*" published in the *Mysore Gazette*, dated 30th May 1940, Part VI pages 1230-1232.

The last date of tender is 12th June 1940.

B. TIRUMALACHAR,
Executive Engineer.

MEDICAL DEPARTMENT.

MINTO OPHTHALMIC HOSPITAL, BANGALORE.

Abstract Notification dated 23rd May 1940.

The attention of the public is invited to the detailed Tender Notice, dated 20th May 1940, calling for tenders for the supply of furniture to the Minto Ophthalmic Hospital, Bangalore. For details please see pages 1232-1233, Part VI of the *Mysore Gazette*, dated 30th May 1940.

B. N. SITARAMIAH,
Secretary.